

**ADVERTISEMENT FOR BIDS**

Separate Sealed BIDS for the CONSTRUCTION OF the Town of Jackson 2018 Spring Street Patching Project consisting of furnishing of all necessary, labor, equipment, transportation, services, and materials required for the installation of approximately 25,000 square feet of asphalt street patching in various location throughout Town.

All patches shall be Machine-laid and will be mechanically ground to a minimum of 4-feet in width and 3-inches in depth. This cost shall include grinding, traffic control, cleanup, stockpiling, and removal/disposal of ground asphalt material. All patches shall include removal of all asphalt and base material to a 3-inch depth by grinding, compaction of sub base, and installation of 3-inch minimum thickness of compacted asphalt patch. All edges and patch bottom surfaces will to be tacked. Patches shall be completed no more than 3-days after grinding has been completed. The removal of ground asphalt from patches shall be completed no more the 4 hours prior to completion of the patch.

Bids will be received by the Town of Jackson, Wyoming, at the office of the Town Clerk until 3:00 P.M. (Local Time), Tuesday, February 13<sup>th</sup>, 2018 and then at said office opened and read aloud.

The CONTRACT DOCUMENTS may be examined and/or obtained at the following location:

Jackson Public Works Shop,  
450 West Snow King Avenue,  
Jackson, WY 83001

There shall be a \$10.00 non-refundable charge for the Bid Documents.

WEATHER PERMITTING, THE OWNER'S DESIRE IS FOR THE PROJECT TO BE COMPLETED BETWEEN APRIL 15<sup>TH</sup> AND JUNE 30<sup>TH</sup>, 2018.

THE OWNER RESERVES THE RIGHT TO REFUSE ANY AND ALL BIDS

Publish: Jackson Hole News and Guide – January 24<sup>th</sup>, 31<sup>st</sup>, and February 7<sup>th</sup>, 2018